

SECTIUNEA TEHNICA CONSTRUIRE TROTUAR

Nr.	Capitol de lucrari	U.M.	Cantitatea
0	1	2	3
1	TSA02B1 - Sapatura manuala de pamant in spatii limitate, avand sub 1.00 M sau peste 1.00 M latime, executata fara sprijini, cu taluz vertical, la fundatii, canale, subsoluri, drenuri, trepte de infratire etc. in pamant necoeziv sau slab coeziv adancime ,0.75M teren mijlociu	mc	36,800 material: manopera: utilaj: transport:
1.1	26100 - Sapator	ora	125,267
2	CO01A1 - Trotuar din beton	mp	92,000 material: manopera: utilaj: transport:
2.1	10173 - Beton preparate	mc	8,280
2.1.1	2100957 - Beton de ciment	mc	8,280
2.2	2100880 - Filer de calcar tip 1 saci S 539	kg	14,260
2.3	2600220 - Bitum pt drumuri tip D 180/200 stas 754	kg	7,820
2.4	2903153 - Scindura rasinoase geluite 10-20X80-120 MM	m	18,400
2.5	2958990 - Lemn de foc foioase tari L 1M livrabil din depozit	kg	7,820
2.6	2200525 - Nisip de rau si lacuri sortat si nespalat, 0.0-7.00 mm	mc	5,336
2.7	6202806 - Apa industriala in cisterne pentru lucrari de drumuri si terasamente	mc	0,920
2.8	19900 - Mozaicar	ora	62,634
2.9	24100 - Pavator	ora	62,634
2.10	20650 - Muncitor de deservire pentru montajul in constructii	ora	83,512
3	TE06C1 - Plasa de armatura sudata tip stnb D=8MM ochiurile 100X100MM	mp	92,000 material: manopera: utilaj: transport:
3.1	2004268 - Plasa sudata pentru B.a. din OL 37 tip 118G-296 S438/3-	buc	7,360
3.2	3803166 - Sirma moale obisnuita D = 1,5 OL 32 S 889	kg	1,380
3.3	15000 - Fierar beton	ora	21,445
3.4	20600 - Muncitor de deservire	ora	21,445

TOTAL 1 (Cheltuieli directe)

Greutate Materiale (tone)	Ore Manopera	Material	Manopera
28,95	376,94	0,00	
Alte cheltuieli directe			
Contribuția asiguratorie pentru	2.2500 %	0,00	
T2 = T1 + Alte cheltuieli directe		0,00	
Cheltuieli indirecte			

